

(ATTENTION CARRIE)



CONCRETE WALL CONSTRUCTION



152 GARARDS FORT ROAD
GARARDS FORT, PA 15334
(724)-966-7166

ESTIMATE FOR:

CHUCK COOLE
6102 CHESTNUT HILLS
MORGANTOWN, W.V. 26505

*New big
11-12-04*

CONSTRUCT SOLID CONCRETE FOUNDATION (CRAWLSPACE)

1. ALL FOOTERS 8 IN. THICK BY 2 FT. WIDE WITH DOUBLE $\frac{1}{2}$ IN. REBAR INSTALLED.
2. CONSTRUCT SOLID CONCRETE FOUNDATION, ALL WALLS 8 IN. THICK HEIGHT OF WALLS FROM 4 FT. TO 8 FT. HIGH. ALL WALLS POURED WITH 4000 P.S.I. CONCRETE WITH FIBER REINFORCEMENT.
3. INSTALL STONE ON INSIDE OF GARAGE, INSTALL PLASTIC VAPOR BARRIER AND POUR CONCRETE FLOOR 4 IN. THICK. ALL OF CONCRETE FLOOR WILL HAVE CONCRETE WIRE REINFORCEMENT.
4. INSTALL TREATED SEAL PLATE ON TOP OF WALL USING 2X8 TREATED LUMBER.
5. FORM AND POUR CONCRETE DRIVEWAY 17 FT. WIDE BY 20 FT. LONG, DRIVEWAY WILL HAVE RETAINING WALL AND ONE SURFACE DRAIN INSTALLED.

TOTAL PRICE OF JOB \$29,300.00

FIRST PAYMENT DUE WHEN FOOTERS ARE POURED	\$14,650.00
FINAL PAYMENT DUE WHEN JOB IS COMPLETED	<u>14,650.00</u>
TOTAL	\$29,300.00

CONTRACTOR
GREGORY SWITALSKI SR.
152 GARARDS FORT ROAD
GARARDS FORT, PA. 15334

W.V. CONTRACTORS NO. 023038