



Heating & Air Conditioning, Inc.

www.groggsh heating.com

588 Harris Highway • Parkersburg, WV 26101 • 304-863-3553

Yellow Brick Building • Old Bridgeport Hill • Clarksburg, WV 26301 • 304-326-0553

October 24, 2008

Customer: Coole

Location: Morgantown

Proposal for Heil 13 SEER R22 Condensing Unit & Air Handler

We propose to furnish and install (1) – Heil 2.5 Ton 13 SEER R22 Condensing Unit with (1) – Heil 2.5 Ton Air Handler with Electric Heat Kit. Furnace and duct work will be located in the basement or crawl space of the home. We will run all duct work and connect branch supply runs to factory installed boots and registers. The supply duct work will be completely insulated, if located in the crawl space. Your electrician will supply the electric to our furnace and condensing unit. The drain for the condensing unit will be run into a condensate pump and connected to a drain pipe. The condensing unit will be set on a poly pad and disconnect box will be mounted. A digital non-programmable thermostat will be installed to the system. All materials and labor included, to completely install the job. *The condensing unit carries a five-year compressor warranty and five-years on all other parts. A one-year labor warranty through Grogg's Heating & Air Conditioning is also included.*

We propose to do the above for the sum of: **\$6,527.00**

***Quote Includes All Duct Work to Completely Install Job (Main Floor Only)**

For Rheem Equipment with R410A Refrigerant: + \$651.00

Warranties: 10-Year Compressor / 5-Year Parts / 1-Year Labor

For Upgrade to Heil Heat Pump System: + \$381.00

For Upgrade to Rheem Heat Pump System: + \$510.00

Respectfully Submitted By:


R. Keith Blair
Branch Manager

I, _____, accept the above proposal, dated _____.

Indoor Comfort. Air Quality. Customer Care.